

# Case Study

## Lincoln Cornhill Quarter



Steintec has been supplying their high performance paving mortars as well as design assistance, equipment and logistical support to the redevelopment of Lincoln Cornhill Quarter which has been under construction since 2017.

The project has involved a number of design, construction and logistical challenges which required collaboration between the designers and the installers with Steintec's technical team providing ongoing assistance.

The large public areas were constructed in phases to minimise disruption to businesses and the public.

Large expanses of paving without unsightly movement joints were created to avoid disrupting the beautiful natural stone layout of the area.

Steintec provided specialist mixing equipment to reduce noise as well as high performance rapid curing bedding, priming and jointing paving mortar to help minimise disruption.

Lincoln Cornhill Quarter has to be one of the most impressive natural stone paving projects of recent years.



### Project Details

Region	UK East Midlands
Location	Lincoln, Lincolnshire
Project Size	1,800 m <sup>2</sup>
Landscape Architect	Re-Form Landscape Architecture
Contractor	Lindum Group
Date Completed	January 2024
Paving Elements	Setts, Slabs
Traffic Load	Pedestrian, Service & Delivery Vehicles
Tools Hired	Baron Forced Action Mixer

### Products Used



tuffbed 2-pack bedding mortar mixed with tuffgrit (1:4)



tuffbond priming mortar



tufftop jointing mortar



tuffset G specialist 3-in-1 mortar

**Steintec**<sup>®</sup>  
high performance paving mortars

1 Northwick Rd  
Canvey Island  
Essex  
SS8 0PU  
**+44 203 598 9800**  
[www.steintec.co.uk](http://www.steintec.co.uk)